

User input indicated by **Orange fields**

User Input	
Zoning lookup	Minimum GI Score
REGEN	0.5

1. Enter Development Site Area m <sup>2</sup> <a href="#">HERE</a> ▶		15000	
Surface Type (see tab for detailed descriptions)	Factor	Proposed Surface Area m <sup>2</sup>	Factor Values
1. Short Lawn	0.3	677.97	203.391
2. Tall Lawn (wild, not mown)	0.5	0	0
Permeable Paving	0.3	1483.69	445.107
Vegetation		0	0
4a. Vegetation-Shrub below 3m	0.4	3502.25	1400.9
4b. Vegetation-Shrub / Hedgerow above 3m	0.5	0	0
4c. Vegetation-Pollinator friendly perennial planting	0.5	525.34	262.67
4d. Vegetation-Preserved hedgerow	1.2	0	0
Trees		0	0
5a. New trees	0.6	304	182.4
5b. Preserved trees	1.2	0	0
7. SuDS intervention (rain garden, bioswale)	0.6	660.94	396.564
Green Roof		0	0
9a. Green Roofs - Intensive green roof (substrate is 200-1200mm in depth)	0.7	2219.06	1553.342
9b. Green Roofs - Extensive green roof (substrate is 80-200mm in depth)	0.6	5458	3274.8
10. Green well	0.4	0	0
11. Retained Open Water	2	0	0
12. New open water	1.5	401.29	601.935
<b>Total Equivalent Surface Area of Greening Factors</b>		<b>15,232.54</b>	

<b>Green Factor Numerator</b>	<b>8321.11</b>
-------------------------------	----------------

Minimum Required GI score	Final GI score	Result
0.5	0.55	Pass

# GREEN SCORE FACTOR 5.0

All strategies have contributed to achieving this score, with every possible greening effort applied wherever feasible. This brownfield site incorporates a range of sustainable measures, including new trees, pollinator-friendly planting, and extensive green roof coverage, enhancing biodiversity and ecological value. SuDS strategies such as rain gardens and bioswales improve water management, while layered low planting—from bulb planting to clipped hedges—creates defined spaces, visual interest, and ecological benefits. These combined efforts showcase a strong commitment to sustainability, ensuring long-term environmental and social value.

Landscape Plans and schedules included in the application, prepared by NMP Landscape Architects includes a detailed schedule of proposed planting and illustrates the location and extent of mown grass, managed long grass, reinforced grass, low ground cover, hedge and tree planting as well as existing trees to be retained where applicable.

Tree species are selected for longevity, suitability to local soil conditions and micro-climate, biodiversity (native species) and where required suitability for proximity to residential buildings. Proposed tree sizes range from heavy standards and multi-stemmed trees to native whip and forestry transplants. There will be a net gain of individual trees in order to improve the species mix and the proportion of native species on site. Typical species are illustrated on the following pages.

Low planting is utilized to make and reinforce sub-spaces within the larger landscape spaces, for visual screening, defensible space, visual interest, ecological purposes and to guide or direct people's movement. The low planting is conceived as subtle layering of greens within the open spaces. The planting is layered as follows; lowest - bulb planting, ground cover planting, highest - clipped hedge planting.

The selection of hard landscape materials is determined by function but also to provide a cohesive palette of materials throughout. Materials are chosen for durability, but where practical are proposed to be constructed in a way which is sensitively integrated with lawn and soft landscape, in order to minimise the impact of hard landscape surfaces. Primary vehicular, pedestrian and cycle circulation are proposed as a durable, limited range of neutral materials with robust construction.

# LANDSCAPE PALETTES

0.  
6

# 6.1 Indicative Hard Landscape Material Approach

## SURFACE FINISHES


Materials have been chosen to be both robust and timeless, provide texture and tone for visually impaired, to tie into the surrounding public realm while also seeking to provide integrated intuitive wayfinding.

Coloured Asphalt




To roads

Coloured Asphalt



To avenues

Coloured Asphalt



To cycle lane

Block Paving



To parking bays

Brushed Concrete



To footpath

Paving Flags



To private amenity

Feature Paving



To pocket park

Precast Concrete Flags



To courtyard

## FURNITURE

Bins, bollards and seating have been selected as appropriate to the design language and surroundings. These for the most part, will be off the shelf products and specified accordingly.

Benches



To pedestrian areas

Bins



To pedestrian areas

Bollards




To road edges

Bike Stand




To bike parking

Tree Guard




To pedestrian areas

Play



Bespoke Imaginative

Exercise



To fitness areas

Ecology



Habitat Opportunities

## 6.2 Indicative Soft Landscape Material Approach


### WOODLAND TREE PLANTING

Informed by the existing and formative tree planting and a native palette the tree planting will bleed into the site and grade out form north to south.

*Fagus sylvatica*



*Betula utilis*



*Pinus sylvestris*



*Sorbus aucuparia*



*Pyrus calleryana*




*Quercus robur*



*Prunus serrula*



*Tilia cordata*




### STREET TREES + SMALL FEATURE TREES + PODIUM TREES PLANTING

Specimen tree planting will provide year long interest and beauty - landmarks in the landscape, to celebrate and identify with.


*Betula jacquemontii*



*Carpinus betulus multistem*



*Cornus sanguinea*



*Pinus sylvestris watereri*




*Acer griseum*




*Magnolia grandiflora*



*Buxus sempervirens*



*Tilia cordata*




### WILDFLOWER & SHRUB PLANTING

To enhance bio-diverse credentials wildflower planting will occupy edges and large swathes of the sites periphery along with shade tolerant understory planting including plant selection to encourage foraging.

*Papaver rhoeas*




*Silene dioica*



*Lotus corniculatus*




*Matricaria chamomilla*




*Ranunculus acris*




*Medicago lupulina*



*Lavandula x intermedia*




*Salvia officinalis*



### WOODLAND UNDERSTORY & SHADE LOVING PLANTING

Woodland areas and shaded gardens will be planted with mix of shade loving plants.

*Polystichum aculeatum*



*Cyathea australis*




*Dicksonia antarctica*



*Dryopteris filix-mas*



*Viburnum davidii*



*Heuchera 'Fireworks'*



*Hosta sp.*



*Pachysandra terminalis*



# Appendix 1 - Soft Landscape Outline Specification

1. Specifications for supply.

1.0 Schedule of supply:

The nursery stock material will be delivered following consultation between the Landscape Architect, landscape contractor and the selected nursery, and the Engineer. Delivery will be at all times by means of covered vehicles, and all plant material will be clearly labeled. The source of origin must be from the selected nursery as no other additional stock from other nurseries will be permitted without prior inspection and approval.

1.1 Programme of Works

The planting works shall be executed at the earliest opportunity.

1.2 Nursery stock:

All plant material shall be good quality nursery stock, free from fungal, bacterial or viral infection, aphids, red spider or other insect pests and any physical damage. It shall comply with the requirements of B.S. 3936: Parts 1-10: 1965 Specification for Nursery Stock, where applicable.

All plants shall have been nursery grown in accordance with good practice and shall be supplied through the normal channels of the wholesale nursery trade. They shall have the habit of growth that is normal for the species. Country of origin must be shown in all cases for species grown from seed.

Unless otherwise stated, the plant materials shall be supplied in accordance with the following codes where stated:

1+0	1 Year old seedling
1+1	1 Year old seedling lined out for 1 year
1+2	1 Year old seedling lined out for 2 years
1+1+1	1 Year old seedling lined out for 1 year, lifted and lined out for one further year
1u1	1 Year old seedling undercut then 1 more year in seedbed.
1u2	1 Year old seedling undercut then 2 more years in seedbed.
0/1	1 Year old Hardwood cutting
0/2	2 Year old Hardwood cutting
2X	Twice transplanted tree
3X	Three times transplanted tree
4X	Four times transplanted tree
P9	Containerised plant in 9cm pot

1.3 Species:

All plants supplied shall be exactly true to name as shown in the plant schedules. Unless stipulated, varieties with variegated and/or coloured leaves will not be accepted, and any plant found to be of this type upon leafing out shall be replaced by the contractor at his/her own expense.

Bundles of plants shall be marked in conformity with B.S. 3936: Part 1: 1965 and B.S. 3936: part 4: 1966. The nursery supplier shall replace any plants which, on leafing out, are found not to conform to the labels. Definitions of all terms used are in accordance with the following British Standards: -

B.S. No. 3936: Part 1: 1965 entitled “Nursery Stock- Trees and Shrubs”

B.S. No. 3936: Part 4: 1966 entitled “ Nursery Stock- Forest Trees”

B.S. No. 3936: 1967 entitled “Specification for Nursery Stock”

2.0 Tree specifications:

Trees shall have a sturdy, reasonably straight stem, and a well-defined straight and upright central leader, with branches growing out of the stem with reasonable symmetry. The crown and root systems shall be well formed. Roots shall be in reasonable balance with the crown and shall be conducive to successful transplantation.

2.1 Standard trees shall have a clear stem 1.70m in height from ground level to the lowest branch, a minimum girth of 8cm measured at 1.00m above ground level and a total height of 2.75-3.00 m.

2.2 Light Standard trees have a clear stem 1.30m in height from ground level to the lowest branch, a minimum girth of 6cm measured at 1.00m above ground level and a total height of 1.80-2.40m.

2.3 Select standard trees shall have a clear stem 1.70 m in height from ground level to the lowest branch, a minimum girth of 10 cm. measured at 1.00.m. above ground level and a total height of 3.0 to 3.5 metres.

2.4 Heavy standard trees shall have a clear stem 1.80-1.90m in height from ground level to the lowest branch, a minimum girth of 14 cm. measured at 1.00.m. above ground level and a total height of 4.0 to 4.5 metres. All trees shall have been undercut a minimum of three times.

2.5 Extra Heavy standard trees shall have a clear stem 2.0m in height from ground level to the lowest branch, a minimum girth of 16 cm. measured at 1.00.m. above ground level and a total height of 4.5 to 5 metres. All trees shall have been undercut a minimum of three times.

2.6 Semi-mature trees shall have a clear stem 2.0m in height from ground level to the lowest branch, a minimum girth, as specified in the Bill of Quantities, measured at 1.00.m. above ground level and a total height of min. 5 metres. All trees shall have been undercut a minimum of three times.

All standards shall be clearly labeled.

2.7 Feathered Trees 180-240cm

Feathered trees shall be not less than four years old, and shall have been transplanted at least three times. Trees of species not listed in BS 3936: Part 4: shall be sturdy, with a balanced root and shoot development. Size shall conform to the schedules.

Trees shall be well furnished with lateral fibrous roots, and shall be lifted without severance of major roots. Roots shall be of the habit normal for the species, without deformation. Transplants shall be wrapped in polythene in bundles of 50 no. and clearly labeled from the time of lifting until planting to conserve moisture.

2.8 Feathered Transplants 120-150cm

Transplants shall be not less than two years old, and shall have been transplanted at least once. Trees of species not listed in B.S. 3936: Part 4: shall be sturdy, with a balanced root and shoot development. Size shall conform to the schedules.

Trees shall be well furnished with lateral fibrous roots, and shall be lifted without severance of major roots. Roots shall be of the habit normal for the species, without deformation. Transplants shall be wrapped in polythene in bundles of 50 no. and clearly labeled from the time of lifting until planting to conserve moisture.

2.9 Feathered Transplants 90-120 cms, 60-90 cm, 40-60 cm, 30-40 cm

Transplants shall be not less than one year old. Trees of species not listed in B.S. 3936: Part 4: shall be sturdy, with a balanced root and shoot development. Size shall conform to the schedules. Trees shall be well furnished with lateral fibrous roots, and shall be lifted without severance of major roots. Roots shall be of the habit normal for the species, without deformation. Transplants shall be wrapped in polythene in bundles of 50 no. and clearly labeled from the time of lifting until planting to conserve moisture.

2.10 Shrubs

(1) Containerised Shrubs shall be of the size specified in the schedules, with several stems originating from or near ground level and of reasonable bushiness, healthy, vigorous and with a sound root system. Pots or containers shall be appropriate to the size of shrub supplied and clearly labeled. Shrubs shall not be pot bound or with girdled or restricted roots.

(2) Bare Root Shrubs shall be of size specified in the schedules, with several stems originating from or near ground level, with reasonable bushiness, healthy, and vigorous. They shall be well furnished with fibrous roots and shall be lifted without severance of major roots. All bare root shrubs shall be wrapped in polythene in bundles of 50 no. and clearly labeled from the time of lifting until planting to conserve moisture.

2.11 Container Grown Conifers:

Conifers shall be of the size specified in the schedules, with one main stem originating from or near ground level and of reasonable bushiness and health, with a well-grown, root system. Pots or containers, where required, shall be appropriate to the size of plant supplied and clearly labeled. Plants shall not be pot bound, or with deformed or restricted roots.

# Appendix 1 - Soft Landscape Outline Specification

## 2.12 Protection:

The interval between the lifting of stock at the nursery and planting on site is to be kept to an absolute minimum. Plants shall be protected from drying out and from damage in transport. All stock awaiting transport shall be protected from the wind and frost and from drying out.

Protection shall include for the supply of stock to site to a suitable heeling-in/ storage area prior to planting. The landscape contractor shall allow for liaison with the site engineer to arrange the heeling-in area/ storage. The contractor shall continue to be entirely responsible for the maintenance of this stock to ensure that at the time of planting the stock complies with the requirements for the supply of nursery stock as per clause 1.0 thereof. No responsibility for the maintenance of the stock will attach to the site engineer whilst the stock is protected on site. No time limit shall attach to the period of protection.

In the event of the Landscape Architect being dissatisfied with the care and attention given to the stocks, following heeling-in, he shall notify the Landscape Contractor who shall take steps to ensure careful heeling-in procedures.

The preparation of the heeling-in area and its subsequent maintenance is the sole responsibility of the Landscape Contractor.

## 2.13 Damage

On completion of lifting of plants in the nursery, any broken shoots or severed roots shall be pruned, areas of damaged bark neatly pared back to sound tissue.

## 2.14 Inspections

The Landscape Architect will inspect the hardy nursery stock on the selected nursery during the execution of the works. Only plants selected and approved in the landscape contractors selected nursery will be accepted on the site.

## 2.15 Delivery and heeling in

All plants will be delivered on a phased basis as called up in advance in agreement with the Engineer, Landscape Architect and the appointed Landscape Contractor. In the event of the Landscape Architect being dissatisfied with the care and attention given to the stocks, following heeling-in, he shall notify the Landscape Contractor who shall take steps to ensure careful heeling-in procedures.

The preparation of the heeling-in area and its subsequent maintenance is the sole responsibility of the Landscape Contractor.

## 3.0 Specifications for site operations:

### 3.1 Setting out:

Setting out shall be in accordance with site meetings with the Landscape Architect, and the drawings listed in the preliminaries. No planting works shall take place when the soil /fill is in a waterlogged condition.

### 3.2 Finished grading:

All planting pits and topsoiled areas disturbed by the landscape contractor shall be left in an even state, with all soil clumps broken up and stones of greater than 50mm diameter shall be removed.

## 4.0 Specifications for Planting and Plant Materials

### 4.1.1 Stakes:

Round stakes shall be of peeled larch, pine or Douglas fir, preserved with a water-borne copper chrome arsenic composition in accordance with I.S. 131. For standard and select standards stakes shall be 1.8m long, 75mm in diameter. Stake all whips and transplants greater than 120cm in height. For all transplants exceeding 120cm height stakes shall be 1.2m long, 37mm x 37mm square. Stakes shall be pointed at the butt end. Set stakes vertically in the pit, to the western side of the tree station, and drive before planting. Drive stake with a wooden maul or cast-iron headed drive. Stakes shall be driven into the excavated planting pit to a depth of:

800mm for Standards/Light Standards/Feathered Trees

1000mm for Heavy Standards

500mm for Whips/Transplants

### 4.1.2 Canes:

Bamboo canes or similar approved shall be used to provide spot spraying location markers for small plants including Pinus, species. The canes are not to be attached to the plants.

## 4.2 Tree ties:

For standard and select standards, tree ties shall be of rubber, PVC or proprietary fabric laminate composition and shall be strong and durable enough to hold the tree securely in all weather conditions for a period of three years. They shall be flexible enough to allow proper tightening of the tie. Ties shall be min. 25mm wide for 120cms height trees and min. 38mm for larger sizes. They shall be fitted with a simple collar spacer to prevent chafing.

Two ties per tree shall be applied to standards; for staked transplants, one tie per tree is required.

Ties shall be nailed to the stake with one galvanised nail.

## 4.3 Protection:

The interval between the lifting of stock at the heeling-in area and planting on site is to be kept to an absolute minimum. Plants shall be protected from drying out and from damage in transport. All stock awaiting planting on site shall be stored in a sheltered place protected from the wind and frost and from drying out.

All transplants shall be wrapped in polythene from the time of lifting to conserve moisture. Except when heeled-in, they shall be protected in polythene at all times until planted into their final position on site.

## 4.4 Damage:

On completion of planting any broken branches shall be pruned, areas of damaged bark neatly pared back to sound tissue.

## 4.5 Watering / Alginure / Fertilisers:

All bare rooted light standards and select standards shall be soaked in water overnight, on site, before planting in a liquid solution containing “Alginure” at the recommended dilution rate. Fertilisers shall conform to BS 5581: 1981. In the case of granular fertiliser being added to plantings, it must be mixed through and incorporated into the base of the planting hole and covered over in order to avoid roots of plants coming in direct contact.

## 4.6 Setting out:

Setting out shall be in accordance with site meetings with the Landscape Architect. Transplants in mixtures shall be planted in staggered rows. Species shall be planted in groups, as indicated in the planting drawings.

No planting shall take place until all planting holes (with ameliorants) have been inspected and approved by the Landscape Architect, or a person appointed by him as a representative, to ensure accordance with the specifications. No planting shall take place when ground conditions are frozen or waterlogged. All planting holes shall be opened and closed on the same day.

Be planted in the centre of the planting pit and planted upright. Stones or other rubbish over 75mm shall be removed. Supply and drive the stake 800mm into the ground for standards, 500mm for other transplants. Backfill planting hole

4.7 Tree planting:  
Trees shall be planted at the same depth as in the nursery, indicated by the soil mark on the stem of the tree. They shall with excavated topsoil, and remove all stones and debris, firming plant into position

### 4.7.1.Select Standards

Excavate tree pits to 800mm x 800mm x 600mm deep, or as approved. The base of the pit shall be broken up to a depth of 80mm and glazed sides roughened. F.Y.M. at the rate of 0.047 cu.m.(equivalent to 60mm deep) and 100gms of 0.10.20 shall be applied to each tree pit prior to planting. Farm manure shall consist predominantly of fecal matter and shall be free of loose, dry straw and undigested hay. It shall be free of surplus liquid effluent. Backfill planting hole with excavated topsoil, and remove all stones and debris, firming plant into position.

### 4.7.2 Heavy and Extra Heavy Standards

Excavate tree pits to 1000mm x 1000mm x 800mm deep, or as approved. The base of the pit shall be broken up to a depth of 100mm and glazed sides roughened. F.Y.M. at the rate of 0.047 cu.m. (equivalent to 60mm deep) and 100gms of 0.10.20 shall be applied to each tree pit prior to planting. Farm manure shall consist predominantly of fecal matter and shall be free of loose, dry straw and undigested hay. It shall be free of surplus liquid effluent. Backfill planting hole with excavated topsoil, and remove all stones and debris, firming plant into position.

### 4.7.2 Semi-mature trees

Excavate tree pits to 1200mm x 1200mm x 1000mm deep, or as approved. The base of the pit shall be broken up to a depth of 200mm and glazed sides roughened. F.Y.M. at the rate of 0.047 cu.m. (equivalent to 60mm deep) and 100gms of 0.10.20 shall be applied to each tree pit prior to planting. Farm manure shall consist predominantly of fecal matter and shall be free of loose, dry straw and undigested hay. It shall be free of surplus liquid effluent. Backfill planting hole with excavated topsoil, and remove all stones and debris, firming plant into position.

### 4.7.3.Light Standard Trees

Excavate tree pits to 500mmx500mmx500xx deep, or as approved. The base of the pit shall be broken up to a depth of 80mm and glazed sides roughened. F.Y.M. at the rate of 0.047 cu.m. (equivalent to 60mm deep) and 100gms of 0.10.20 shall be applied to each tree pit prior to planting. Farm

# Appendix 1 - Soft Landscape Outline Specification

manure shall consist predominantly of fecal matter and shall be free of loose, dry straw and undigested hay. It shall be free of surplus liquid effluent. Backfill planting hole with excavated topsoil, and remove all stones and debris, firming plant into position.

4.8 Feathered Trees 180-240cm, container grown conifers (>2l)

Excavate tree pits to 400mm x 400mm x 400 mm deep, or as approved (slit or notch planting are not acceptable planting methods). The base of the pit shall be broken up to a depth of 80mm and glazed sides **roughened. Trees shall be planted at the same depth as in the nursery and backfilled with compound fertiliser 0.10.20 at the rate of 50gm per tree and 0.020m<sup>3</sup> of Mushroom Compost or similar approved. Backfill planting hole with excavated topsoil, and remove all stones and debris, firming plant into position.**

**4.9 Feathered Whips 120-150 cm:**

**Excavate tree pit to depth of 300mm x 300mm x 300mm deep, or as approved (slit or notch planting are not acceptable planting methods). Excavation to be achieved by machine digging or auguring methods, approved by the Landscape Architect. The base to be broken up to a depth of 60mm and glazed sides roughened. Whips to be planted at same size as in the nursery. Apply 60gm 0.10.20 and 0.020m<sup>3</sup> of Mushroom Compost or similar approved. Per tree pit to plants. Stakes 1.2m high x 37mm diam. Backfill planting hole with excavated topsoil, and remove all stones and debris, firming plant into position.**

4.10 Feathered Whips and Transplants 90-120cm, 60-90 cm, 40-60cm, 30-40cm, container grown conifers (<2l size) and container grown shrubs (<2l size):

Excavate planting hole to a depth of 300mm x 300mm x 300mm deep; the base to be broken to a depth of 50mm and glazed sides roughened (slit or notch planting are not acceptable planting methods). Excavation to be achieved by machine digging or auguring methods, approved by the Landscape Architect. Apply 30gm 0.10.20.per planting pit. Backfill planting hole with excavated topsoil, and remove all stones and debris, firming plant into position.

4.11 C. G. Shrubs / C. G. Wall Shrubs / C.G. Climbers:

Excavate planting hole to a depth of 300mm x 300mm x 300mm deep; the base to be broken to a depth of 50mm and glazed sides roughened. The following products are to be supplied and incorporated in to the bottom 100mm of topsoil at the base of the planting pit and in to the topsoil for back-filling around each plant: (1)Seanure soilbuilder as supplied by Farmura @ 1.5Kg per cu.m of topsoil, (2) clean and friable green waste compost @ 25 Kg per cu.m of topsoil and (3) Sierrablen Flora 15:9:9 slow release fertiliser @ 70 grams per m<sup>2</sup> Backfill planting hole with excavated topsoil, and remove all stones and debris, firming plant into position.

4.12 Grassing

All grass areas to be ripped with a tractor mounted tine prior to rotovating. The contractor shall grade off all areas to smooth flowing contours, removing all stones greater than 10mm diameter and tip off site. All hollows to be filled in. Roll all areas with a roller as approved. Following the completion of final grading and raking, the area is to be left fallow for a period of 14 days. Spray with 'Basta' at recommended rates, and seed with fine grass mix at a rate of 35gr/Sq.m together with fertilizer 10:10:20 at a rate of 50gr/Sq.m use Coburns Irish premier low maintenance mixture or other as approved by the Landscape Architect.

4.12.1 Grass cutting

Grass cutting shall be carried out during the three year maintenance period and is defined into three categories:

4.12.2 Regular grass cutting

Shall be carried out to the frequencies indicated in the Bill of Quantities. Attention to neat and tidy cutting shall be required to all areas. Sightlines, as set out with the Engineer, at junctions and roundabouts must be kept clear of vegetation at all times.

GENERAL

Upon completion of planting, all pits shall be raked over lightly to leave an even surface and neat appearance. All stones greater than 50mm dia. to be removed. Provision should be made for the watering of light and select standards during periods of prolonged drought in the first year following planting.

4.13 Inspections:

The Landscape Architect will inspect the site with the Landscape Contractor during the execution of the works and following maintenance visits.

4.14 Presentation of certificates:

The Landscape Contractor shall present for the Landscape Architect's inspection, all seed and fertiliser bags, together with their markings. If requested, the contractor shall furnish the Landscape Architect with receipts of purchase for these respective materials.

4.15 Spraying:

1) Following planting of embankments, slopes etc., weed free circles to be formed around individual plants, as directed, using an approved broad-spectrum contact herbicide, as approved by the landscape architect, in mid-spring following planting. Herbicide to be applied using controlled drop applicator containing a dye to indicate areas sprayed. In areas where grass is excessively long, such grass will be strimmed off and collected prior to spraying. The contractor shall be responsible for keeping the ground (1m diameter circle) around all planted material weed free by means of herbicidal application, using approved sprays, during the course of the contract. Weeds to be removed include grasses ,broad-leaved annual and perennial weeds and all noxious weeds.

2) Selective spot spraying will be carried out to all grassed areas, whether planted or unplanted through the application of contact herbicide to control broad-leaved annual and perennial weeds, including thistle, dock and ragwort. Contact herbicide to be approved by the landscape architect prior to application. Herbicide to be applied using controlled drop applicator containing a dye to indicate areas sprayed. The contractor shall allow for the removal of gorse by cutting, as required prior to spraying to ensure its eradication from all grassed areas for the duration of the contract.

3) The boundary hedgerows shall be kept weed free by herbicidal application by forming a 300mm wide spayed strip along the full length of each respective hedgerow. Approved herbicide (broad-spectrum contact herbicide) to be applied using controlled drop applicator containing a dye to indicate areas sprayed. Spraying of planted areas on roundabouts is also included in this spraying application.

4) Such routine spraying (1, 2 and 3 above) shall be carried out during maintenance visits over the three-year period. No spraying shall take place during adverse weather conditions or at times not recommended by the manufacturer.

4.16 Cutting back:

Plants for cutting back/tip pruning shall be cut back after inspection by the Landscape Architect. This work to be carried out initially following planting for plants suffering from wind damage.

4.17 Mulching

Mulching may be considered as an optional factor that may be implemented. Mulch shall be from coniferous trees. It shall be shredded, but not pulverised, so that no dimension exceeds 75mm. Bark shall have been composted for a min. of 3mths. In the case of areas requiring mulch the depth of bark shall measure 30 mm.

4.18 Ground finish:

Upon completion of planting, all ground finish shall include for the removal of stones greater than 50mm excavated during the course of the digging for planting purposes.

# Appendix 2 - Hard Landscape Outline Specification

## PAVING & KERBS

### FOOTPATHS

General: Public footpaths, roadways, kerbs etc. shall be constructed in accordance with the requirements of the Roads Maintenance Dun Laoghaire Rathdown County Council.

Accuracy of Levels and Alignment: The levels of paths and paving shall be carefully set out and frequently checked. All care shall be taken to ensure that the correct cross sections are maintained. The finished face of paths shall be formed so as to provide adequate fall and satisfactory run off to surface water outlets, gullies, etc. Cross-falls of paths shall be carried without break across verges and kerbs to prevent ponding of water between back of kerb and path.

Sub-Base: Granular material shall comply with Clause 804 of the D.o.E. Specification for Roadwork's and shall be spread uniformly over the formation and compacted by vibrator roller. Rolling shall continue until there is no movement under the roller. The finished surface of the compacted sub-base shall be parallel to the proposed finished surface of the footpath. The surface levels for each layer shall not deviate from the design levels by more than +15mm or -15mm.

For sub-base thickness in paved areas see area engineers spec. and attached following schedule. Each contractor shall do all necessary tests to ensure a well compacted, plain even surface on all areas with traffic movement. If paving shows settling after 1 year which normally is related to an insufficient depth and compaction of the sub-base the contractor shall rebuilt the failed area to his own cost.

#### Use of Surfaces by Construction Traffic:

Constructional traffic used on pavements under construction shall be suitable in relation to the courses it traverses so that damage is not caused to the sub-grade. Where damage is caused to the formation of the sub-grade in strength or level the damaged area shall be excavated for an area and depth which shall be determined by the Architect and this area shall be filled to the required levels with crushed rock of 50mm maximum size. The degree of compaction for this area shall be the same as that specified for the remainder of the formation. All this excavation and making good of damaged areas shall be carried out at the expense of the Contractor. Where damage is caused to the sub-base, the damaged area shall be made good as noted above, using the material of which the sub-base is composed. The wheels or tracks of plant moving over the various pavement courses shall be kept free from deleterious materials.

### MODULAR PAVING

Concrete Pavers Precast concrete pavers shall conform to the requirements of BS 6717 Part 1. Ensure that sub-bases are suitably accurate and to specified gradients before being laid.

Sample: Before placing orders submit representative samples for approval. Ensure that delivered materials match sample.

Laying Generally:

#### 1. Laying Specification

1.1 Paving blocks/bricks shall be laid to the requirements of Part 3: 1997, BS 7533, except that the lip onto gully gratings is modified to 5 - 6 mm.

Note, in particular, the following requirements of Part 3.

- i. The difference in level between two adjacent blocks shall not exceed 2 mm.
- ii. The finished pavement surface shall not deviate more than 10 mm under a 3m straight edge.
- iii. The accuracy of cutting a block should be such that the resulting joint should not exceed 5 mm.
- iv. The surface course should be between
  - (a) 3 - 6 mm above drainage channels
  - (b) 5 - 10 mm above gullies ("BRL modify this to 5 - 7 mm above gullies to reduce "trips")
- v. The surface course should be inspected soon after completion and at regular intervals thereafter - additional sand should be brushed in where necessary.

1.2 The surface course for chamfered units should be 3 - 5 mm above the kerb to facilitate surface drainage. The surface course for non-chamfered units should be 2 mm above the kerb to facilitate surface drainage.

1.3 When paving units need to be trimmed, pieces with a dimension less than 50 mm should not be used.

#### 2. Drainage Channels

2.1 Where paving blocks are used in a channel, they shall be laid on freshly mixed moist 3:1 sand-cement mortar. The mortar should have thickness between 10 mm and 40 mm. Vertical joints should be filled with 3:1 wet sand-cement mix.

2.2 Mortar, which has been mixed for over 2 hours, should be discarded.

2.3 The mortar should be laid on a previously prepared concrete base as per construction drawing detail. Select blocks/paviors vertically from at least 3 separate packs in rotation, or as recommended by manufacturer, to avoid colour banding. Lay blocks/paviors on a well graded sand bed and vibrate to produce a thoroughly interlocked paving of even overall appearance with sharp sand filled joints and accurate to line, level and profile. Refill joints once a week three weeks after first fill. Commencing from an edge restraint lay blocks/paviors hand tight with a joint width of 2-3mm for pedestrian use and 3-5 mm for areas with traffic. Maintain an open working face and do not use mechanical force to obtain tight joints. Place blocks/pavers squarely with minimum disturbance to bedding. Supply blocks/paviors to laying face over newly laid paving but stack at least 1 m back from laying face. Do not allow plant to traverse areas of uncompacted paving. Continually check alignment of pavers with string lines as work proceeds to ensure maintenance of accurate bond. Infill at edge restraints as work proceeds. Wherever the type of bond and angle of edging permit, avoid very small infill pieces at edges by breaking bond on the next course in from the edge, using cut blocks/pavers not less than 1/3 full size. Cut stones shall be rectangular or trapezoidal; the smallest point shall be a minimum of 35mm. (May be pavers have to be turned by 90 deg.) Half stones shall be cut at manufacture. Thoroughly compact blocks/pavers with vibrating plate compactor as laying proceeds but after infilling at edges. Apply the same compacting effort over the whole surface. Do not compact within 1 m of the working face. Do not leave uncompacted areas of paving at the end of working periods, except within 1 m of unrestrained edges. Checks paving after compacting first few metres, then at frequent intervals to ensure that surface levels are as specified; if they are not, lift blocks/pavers and relay. Brush sharp sand into joints, revibrate surface and repeat as required to completely fill joints. Make sure that paving is held by a kerb on both sides before vibration to avoid uneven joints. Avoid damaging kerb haunching and adjacent work during vibration. Do not begin vibration until kerbs have matured. The paving pattern will be stretcher bond, make sure that the joints will be in straight line after vibrating. Also ensure joints are off equal width. The block pavement shall have a surface regularity/ flatness tolerance of less than 10 mm under a 3 m straight edge.

Sample: Before placing orders submit representative samples for approval. Ensure that delivered materials match sample.

### PRECAST CONCRETE FLAGS

Pre-cast Concrete Flags:

1. Precast concrete flags shall be laid to the requirements of BS 7533 Part 4.

Note the following selected items from BS 7533, Part 4.

- The difference in level between two adjacent flags should not exceed 3 mm.
- The top surface of the paving units should stand 3 - 6 mm above the drainage channel.
- A 30 - 50 mm (compacted thickness) of the sand laying course is given as suitable (for narrow joints)

2. Flags should be laid with narrow joints (2 - 5 mm). Joints should be filled with dried sand (conforming to table 4 of the code), or as determined by the Landscape Architect.

### KERBS

Kerbing General: Kerb radii shall be in accordance with Architects and Engineers drawings. Use radius kerbs for all new kerbs.

Laying Generally:

Natural stone and precast concrete kerbs shall meet the requirements of BS 435 and BS 7263-1.

1. Precast concrete kerbs shall be laid to the requirements of BS 7533, Part 6.
2. Units shall be laid on fresh concrete or mortar bed and adjusted to line and level.
3. Concrete for foundations and haunching shall be to BS 5328.
4. Bedding mortar shall be freshly mixed, moist 3:1 sand-cement between 12 and 40 mm thick.
5. Kerbs shall be backed with concrete as per drawing.
6. Radius kerbs shall be used on radii of 12 m or less.
7. Kerbs should not deviate from the required level by more than 6mm.
8. Kerbs should not deviate by more than 3 mm under a 3 m straight edge.
9. Open-jointed kerbs should have joints of 2 - 4 mm wide.

Mortar jointed kerbs should have joints of 7 - 10 mm wide filled completely with 3:1 sand-cement mortar, and finished to give a smooth flush joint or as specified by the Landscape Architect.



# Appendix 3 - Programme For Implementation, Maintenance + Defects Period

5.0 Maintenance:

5.1 Period:

The Contractor shall be responsible for aftercare of the completed works for 1 Year from the date of completion of planting. Subject to satisfactory performance the maintenance contract may be extended for two further periods of 12 months. Maintenance in years 2 and 3 shall be provisional. Maintenance during years 2 and 3 may be assigned directly. This will include grass cutting, weed control of all planted areas, litter clearance and watering of Select Standard trees during dry weather.

5.2 Organisation:

The aftercare programme will be organised as follows:-

- (1) Scheduled operations, in whose timing the contractor will be permitted some flexibility and which will be the basis of payment to the Contractor.
- (2) Performance standards, which the Contractor is required to meet at all times, and on which his performance will be assessed.
- (3) Critical dates, by which time scheduled operations, shall have been completed, and at which performance will be assessed.

5.3 Performance standards:

Shrub, woodland and hedgerow planting to be maintained in accordance with specifications e.g. spraying, firming, tree tie adjustment. Weeds shall not cover more than 20% of the ground surface within planting areas and the maintained 1m diameter weed free circles at any time, and neither shall they exceed 100mm in height. Weeds shall be treated before they establish.

Within grass areas noxious and competitive weeds shall not be allowed to establish and all perennial weeds shall be spot treated at each maintenance visit, 3 times per year.

5.4 Watering:

The contractor is responsible for the survival of all plants during the maintenance period. Apply water to moisten full depth of root run using proprietary irrigation system. Avoid washing or compaction of the soil surface. The Landscape Contractor is responsible for informing the Landscape Architect if the plants require watering. A minimum of 16 no. waterings year1, 8 no. year 2, 4 no. year 3. Prior notification to the landscape architect and a record of attendance will be requested for each visit. Spot checks will be made to ensure full compliance with this condition.

5.5 PROGRAMME

Year One (After Planting): Period of 12 months from date of practical completion

5.5.1 By end of May (Year One):

Application of herbicide agreed with Landscape Architect to all planting areas. Protect all plants. Hand weed all large weeds too close to nursery stock for safe treatment. Strim long grass prior to spray application. Provision for 1 no. visit for spot weed control application to areas where perennial weeds are apparent in the grass sward. Tip prune, firm plants. Grass cutting. All necessary cultural/husbandry methods to be completed in order to leave the sites in a clean, orderly and tidy manner. Water select standard trees.

Critical date: 30 May (Year One)

5.5.2 By end August (Year One):

Application of herbicide agreed with Landscape Architect to all planting areas. Protect all plants. Hand weed all large weeds too close to nursery stock for safe treatment. Provision for 1 no. visit for spot weed control application to areas where perennial weeds are apparent in the grass sward. All necessary cultural/husbandry methods to be completed in order to leave the sites in a clean, orderly and tidy manner. Grass cutting. All necessary cultural/husbandry methods to be completed in order to leave the sites in a clean, orderly and tidy manner. Water select standard trees.

Critical Date: 30 August (Year One)

5.5.3 October (Year One):

Remove dead plants after Landscape Architect's inspection.

5.5.4 November (Year One):

Replacement planting. Tree care shall mean pruning deciduous trees including those of hedgerow form when dormant to promote open frame works in the crown. Remove all suckers and dead branches, and branches that are encroaching on to footpaths should be cut back to point of branching.

5.5.5 By end December:

Application of herbicide agreed with Landscape Architect to all planting areas. Grass cutting. All necessary cultural/husbandry methods to be completed in order to leave the sites in a clean, orderly and tidy manner. Water extra heavy standard trees, standard trees.

Critical Date: 30 December (Year One).

5.5.6 Year 2

As year 1.

5.5.7 Year 3

As year 1. Hedgerow to be fully pruned at end of season.

5.5.8 Sweeping and Cleaning

Sweeping shall mean sweeping of the footpaths, playing courts, car parks and the schools road network and removal of all grit rubbish moss and leaves, keeping the hard landscaped areas of the site in a neat and tidy manner. Number of sweepings per annum -12no.

Cleaning shall mean the removal of paper, plastic bags and all other rubbish from grassed areas, roads, car parks, playing courts, shrubbery's, hedging etc. or any part of the school grounds. This operation shall be carried out twice a month.

All dirt and rubbish to be removed off site to a tip to be provided by the Landscape contractor.

Autumn leaves shall be swept on a weekly basis from end of October to mid-November (three weeks). Any additional cleaning and sweeping deemed necessary, during the year, and requested will be paid for at a pro rata basis to the rates for the programmed maintenance schedule.

5.5.9 Other Maintenance Works

All grassed areas are to be edged 3 times a year using a machine and are not to be sprayed.

Carry out any other maintenance to ensure the works are kept in a satisfactory state during the defects liability period.

# Appendix 3 - Programme For Implementation, Maintenance + Defects Period

5.0 Maintenance:

5.1 Period:

The Contractor shall be responsible for aftercare of the completed works for 1 Year from the date of completion of planting. Subject to satisfactory performance the maintenance contract may be extended for two further periods of 12 months. Maintenance in years 2 and 3 shall be provisional. Maintenance during years 2 and 3 may be assigned directly. This will include grass cutting, weed control of all planted areas, litter clearance and watering of Select Standard trees during dry weather.

5.2 Organisation:

The aftercare programme will be organised as follows:-

- (1) Scheduled operations, in whose timing the contractor will be permitted some flexibility and which will be the basis of payment to the Contractor.
- (2) Performance standards, which the Contractor is required to meet at all times, and on which his performance will be assessed.
- (3) Critical dates, by which time scheduled operations, shall have been completed, and at which performance will be assessed.

5.3 Performance standards:

Shrub, woodland and hedgerow planting to be maintained in accordance with specifications e.g. spraying, firming, tree tie adjustment. Weeds shall not cover more than 20% of the ground surface within planting areas and the maintained 1m diameter weed free circles at any time, and neither shall they exceed 100mm in height. Weeds shall be treated before they establish.

Within grass areas noxious and competitive weeds shall not be allowed to establish and all perennial weeds shall be spot treated at each maintenance visit, 3 times per year.

5.4 Watering:

The contractor is responsible for the survival of all plants during the maintenance period. Apply water to moisten full depth of root run using proprietary irrigation system. Avoid washing or compaction of the soil surface. The Landscape Contractor is responsible for informing the Landscape Architect if the plants require watering. A minimum of 16 no. waterings year1, 8 no. year 2, 4 no. year 3. Prior notification to the landscape architect and a record of attendance will be requested for each visit. Spot checks will be made to ensure full compliance with this condition.

5.5 PROGRAMME

Year One (After Planting): Period of 12 months from date of practical completion

5.5.1 By end of May (Year One):

Application of herbicide agreed with Landscape Architect to all planting areas. Protect all plants. Hand weed all large weeds too close to nursery stock for safe treatment. Strim long grass prior to spray application. Provision for 1 no. visit for spot weed control application to areas where perennial weeds are apparent in the grass sward. Tip prune, firm plants. Grass cutting. All necessary cultural/husbandry methods to be completed in order to leave the sites in a clean, orderly and tidy manner. Water select standard trees.

Critical date: 30 May (Year One)

5.5.2 By end August (Year One):

Application of herbicide agreed with Landscape Architect to all planting areas. Protect all plants. Hand weed all large weeds too close to nursery stock for safe treatment. Provision for 1 no. visit for spot weed control application to areas where perennial weeds are apparent in the grass sward. All necessary cultural/husbandry methods to be completed in order to leave the sites in a clean, orderly and tidy manner. Grass cutting. All necessary cultural/ husbandry methods to be completed in order to leave the sites in a clean, orderly and tidy manner. Water select standard trees.

Critical Date: 30 August (Year One)

5.5.3 October (Year One):

Remove dead plants after Landscape Architect's inspection.

5.5.4 November (Year One):

Replacement planting. Tree care shall mean pruning deciduous trees including those of hedgerow form when dormant to promote open frame works in the crown. Remove all suckers and dead branches, and branches that are encroaching on to footpaths should be cut back to point of branching.

5.5.5 By end December:

Application of herbicide agreed with Landscape Architect to all planting areas. Grass cutting. All necessary cultural/husbandry methods to be completed in order to leave the sites in a clean, orderly and tidy manner. Water extra heavy standard trees, standard trees.

Critical Date: 30 December (Year One).

5.5.6 Year 2

As year 1.

5.5.7 Year 3

As year 1. Hedgerow to be fully pruned at end of season.

5.5.8 Sweeping and Cleaning

Sweeping shall mean sweeping of the footpaths, playing courts, car parks and the schools road network and removal of all grit rubbish moss and leaves, keeping the hard landscaped areas of the site in a neat and tidy manner. Number of sweepings per annum -12no.

Cleaning shall mean the removal of paper, plastic bags and all other rubbish from grassed areas, roads, car parks, playing courts, shrubbery's, hedging etc. or any part of the school grounds. This operation shall be carried out twice a month.

All dirt and rubbish to be removed off site to a tip to be provided by the Landscape contractor.

Autumn leaves shall be swept on a weekly basis from end of October to mid-November (three weeks). Any additional cleaning and sweeping deemed necessary, during the year, and requested will be paid for at a pro rata basis to the rates for the programmed maintenance schedule.

5.5.9 Other Maintenance Works

All grassed areas are to be edged 3 times a year using a machine and are not to be sprayed.

Carry out any other maintenance to ensure the works are kept in a satisfactory state during the defects liability period.